

4

3

2

1

F

F

E

E

D

D

C


C

B

B

A

A



SIDE ELEVATION

SCALE 1:10

ANTI SINK PLATE DETAIL

SCALE 1:10

ISOMETRIC ELEVATION

SCALE 1:10

SUPPLIED WITH 4 x M24 X 100MM LENGTH GRADE 8.8 GALVANIZED BOLTS WITH FLAT WASHER (FITTED)

STANDARDS

- ALL PRODUCTS TO CONFORM TO THE FOLLOWING AUSTRALIAN STANDARDS.
- * AS 1170.2 Structural design actions - Wind actions.
 - * AS 1554(set) Structural steel welding set.
 - * AS 2159: Piling - Design & Installation.
 - * AS 2870: Residential slab footings - Construction.
 - * AS 3600: Concrete structures.
 - * AS 3678: Structural steel - Hot rolled plates, floorplates and slabs.
 - * AS 4680: Hot dip galvanized (Zinc) Coatings on fabricated ferrous articles.
 - * AS/NZS 4671: Steel reinforcing materials.
 - * AS/NZS 4600: Cold formed steel structures.



G & S Industries
 97 GUTHRIE STREET,
 OSBORNE PARK W.A. 6017
 PH : +6108 9446 8044
 EMAIL: sales@gsindustries.com.au
 WEB: www.gsindustries.com.au

PROPRIETARY AND CONFIDENTIAL	
THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF G&S INDUSTRIES. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF G&S INDUSTRIES IS PROHIBITED.	
SCALE: AS SHOWN	PRODUCT WEIGHT: 82kg.
PRODUCT FINISH: HOT DIPPED GALVANIZED	
CUSTOMER APPROVAL:	
CUSTOMER NAME / PROJECT:	

NAME	DATE	PART NUMBER : DBSHAFT
DRAWN N. A.	14.10.2022	
CHECKED S. G.	14.10.2022	
APPROVED R. G.	14.10.2022	
COPYRIGHT		
THIS DOCUMENT IS PRODUCED BY G&S INDUSTRIES MUST NOT BE COPIED, TRACED, REPRODUCED, OR LENT WITHOUT WRITTEN CONSENT		

TITLE : DIRECT BURIAL SHAFT SUIT FIXED OR MID HINGED POLES	
AUGURED FOUNDATION HOLE TO BE 600MM IN DIAMETER X 1870MM DEPTH. BACKFILL MATERIAL TO BE CLEAN SAND FILL COMPACTED TO MIN 90% OF MAXIMUM DRY DENSITY AS SPECIFIED IN THE RELEVANT SUBSET OF AS1289. MAXIMUM CLAY CONTENT OF THE BACKFILL MATERIAL TO BE LESS THAN 5%.	
SIZE A4	DWG. NO. ZLRG2767
	REV. 0

4

3

2

1